



**NOTES:**

1. METER SOCKET TO BE SECURED TO CONCRETE OR MASONRY HOUSE WALL WITH 1/4" x 1-3/4" LONG HEXHEAD TAPCON ANCHOR AND 1/4" FLAT WASHER OR 1/4" x 2" LONG LAG BOLT AND LEAD SLEEVE. MAXIMUM 4 ANCHORS OR LAG BOLTS TO BE USED TO SECURE METER SOCKET.
2. ELECTRICAL SAFETY AUTHORITY CONNECTION AUTHORIZATION REQUIRED PRIOR TO ENERGIZING EITHER INSTALLATION.
3. CUSTOMER REQUIRED TO ENTER INTO A CONNECTION AGREEMENT WITH HYDRO ONE BRAMPTON PRIOR TO ENERGIZING EITHER INSTALLATION.
4. DISCONNECT SWITCH TO BE LOCKABLE BY HYDRO ONE BRAMPTON.
5. LABELS REQUIRED TO SHOW IMPORT METER.
6. LABELS REQUIRED TO SHOW EXPORT METER.

APPROVED IN ACCORDANCE WITH REGULATION 22/04

CHECKED: *W. Ron*

APPROVED: *[Signature]*

ORIGINAL ISSUE: SEPTEMBER 08, 2009

**O/H SERVICE RESIDENTIAL  
MICROFIT SOLAR GENERATION  
( PARALLEL CONNECTION )**